



- All posts set in concrete
- 8' post spacing
- 3 rail - 1 roll / 4 rail - 1.5 rolls
- Lean posts 1" away from direction of pull
- Diameter X number of rails = total # of rolls

